



BAFRA PLAIN LEFT BANK IRRIGATION CONSTRUCTION



Central Blacksea Region
Samsun - Bafra





Employer : GENERAL DIRECTORATE OF STATE HYDRAULIC WORKS
Contract date : 04.02.1996
Project cost : 2 982 600 000 000,00 TL (1996 unit prices)
 [50 126 888,62 US \$]

The construction of left bank irrigation work of Bafra Plain Irrigation Main Project, 2nd Section, which is aiming to irrigate 47 724 ha entire agricultural area, is continuing. With this construction it is planned to irrigate 19 500 ha area, which is under the main channel. The irrigation network consists mainly canalets and classical systems. The water source of the project is Derbent dam reservoir and the water is supplied to the main channel through the tail water of Derbent HEPP.

The canalet production of this project is performed in the factory installed for the right bank irrigation project.

Within this work the following items are performed;

Main channel	: 52 000 m
Spare channel	: 200 000 m
Canalet network	: 300 000 m
Main and spare drainage channel	: 156 000 m
Tertiary drainage channel	: 385 000 m
Drainage pumping station	: 3 ea

