


## BEYKÖY HEPP AND TRANSMISSION CHANNEL CONSTRUCTION




Central Anatolia Region Sakarya River - Yenice Dam











(DSI)

**Contract date** : 26.01.1987 **Work completion date** : 07.07.1998

**Project cost** : 25 922 182 000,00 TL (1986 unit prices)

[45 167 247.40 US \$]

Within this project, a HEPP building and  $14\,438\,\text{m}$  long headrace tunnel, taking  $85\,\text{m}^3/\text{day}$  water from the tail water of Yenice Dam, located on Sakarya river, were constructed and the plant will generate  $140\,000\,000\,\text{kWh/year}$  power.

The performed works are;

Conduit : Total 3047 m long and 3.70 m inner radius Headrace Tunnel : Total 236 m long and 3.70 m inner radius

Open Channel : Paved trapezoidal 10 305 m long, 7.00 m wide, 4.20 high

channel

Power Plant : Forebay, penstocks and power plant with 3 units and total 15 MW

installed power, water intake structure, spillway, water channel excavation works were performed and its mechanical equipments

were completed.



